BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT18521/CALL-2

APPROVED SCHEDULE - B

E/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Improvements to Roads & Drains to GKVK Road(Shanimahathma Temple Road) Thindlu Village in ward No. 09 Vidyaranyapura sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of C SHIVARAJU		
				In Figures		In Words
1	376.28	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	83.08	31261.34	Rupees Eighty Three and Eight Paise Only
2	675	Removing B.S Slab of Drain and stacking etc complete as per specifications and directions of engineer in charge of the work	Sqm	63.66	42970.50	Rupees Sixty Three and Sixty Six Paise Only
3	675	Refixing stone slabs of drains and pointing in C.M (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	78.76	53163.00	Rupees Seventy Eight and Seventy Six Paise Only
4	1875	Scarifying kankar/gravel/metal crust upto 150mm thick with pick axes and disposal of stuff within a lead of 100 meters including cost of all labour charges etc complete as per specifications and directions of engineer in charge of the work	Sqm	25.89	48543.75	Rupees Twenty Five and Eighty Nine Paise Only
5	335.25	Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1712.25	574031.81	Rupees One Thousand Seven Hundred Twelve and Twenty Five Paise Only
6	2347.5	Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WBM, WMM including cleaning of road surface and spraying primer at the rate of 0.60 Kg / sqm using mechnical means etc complete as per specifications and directions of engineer in charge of the work	Sqm	32.37	75988.58	Rupees Thirty Two and Thirty Seven Paise Only
7	93.9	Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve, the desired compaction as per MORTH specification clauses No. 500.9 complete in all respects complete as pr specifications. Using 100/120 TPH capacity H.M.P with sensor paver Gr-II (30 mm to 45 mm) with 6 % CRMB 55 etc complete as per specifications and directions of engineer in charge of the work	Cum	11831.44	1110972.22	Rupees Eleven Thousand Eight Hundred Thirty One and Forty Four Paise Only
8	376.28	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 11.90 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	106.23	39972.22	Rupees One Hundred Six and Twenty Three Paise Only
					1976903.42	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

20/7